



Presented by: Larry Jorgensen January 12-13, 2021



Scheduling Requirements (MWs) Reliability Requirements 110 100 Regulation Spinning Reserve 10 Islanding Operation for N-1 Avg Annual Islanding – 4 Wks Bradley outages – at least 1 Wk/yr Islanding Cost \$23,800 / day Regulation Cost \$32,313 / yr. Spinning Reserve Cost up to Tie In Service Islanded \$17,000 / month ■ Regulation Down ■ Base Load ■ Regulation Up Spin



Rates / Reliability Balance



- In order to respond to a N-1 event, HEA must balance between economics and reliability.
- HEA operates with 3 generation sources (generating units or tie) for reliability.



BESS RFP Specification

- System Regulation of ±2.5 MWs
- Spinning Reserve of 10 MWs for 15 minutes.
- Emergency Reserve of 45 MWs for 15 minutes.
- Dispatchable from SCADA.
- EPC (Engineer, Procure, Construct) bid.



System Operation w/BESS

- Regulation, Spinning Reserve, and Emergency Reserve provided by BESS.
- Islanding or Bradley outages no longer requires starting a second thermal unit.
- Potential to integrate Renewables.
- Potential to sell Spin/Regulation.




Risk Management Tool

- Protects against tie line outages,
 Bradley outages, wildfires, etc.
- Provides system stability (reducing frequency swings and load sheds).
- Helps to stabilize COPA during island events.



Scope of Work

- Tesla Megapack Batteries
 (integrated chargers and inverters, control system and monitoring).
 - HEA Balance of Plant design, procurement & construction (transformers, breakers, interconnection to Soldotna Substation).



Tesla MegaPack





Site Layout - Oct. 2020





Scope of Supply & Services

- MegaPack (2-hour) Batteries Delivered to Site
 93 MWh total capacity.
- Tesla's Site Controller & PowerHub Pro Control Software with HMI.
- Fire Detection System.
- Transformers (19 480/24 kV), (GSU 24 kV/115 kV).
- Power Distribution Center.
- Field Network Enclosures.
- 115 kV Breaker.
- Commissioning, Startup and Testing.



Schedule

- HEA target substantial completion by June 30, 2021.
- BESS testing and commissioning 30 to 45 days.
- BESS fully operational by mid August 2021.



Thank You!